

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk Bldg., Wichita, Kansas


12-25-13W

CONTINENTAL OIL CO.
 S.M. McCune No. 3.

SEC. 12 T. 25 R. 13 W
 NW SE NE
 990' N 990' W E 1/4 Cor.

Total Depth. 4094' (DF 4092)
 Comm. 6-13-43 Comp. 7-30-43
 Shot or Treated.
 Contractor. Parker Drlg. Co.
 Issued. 9-4-43

County. Stafford



CASING:
 10 3/4" 283' Cem.
 7" 4078' Cem.

Elevation.

Production. Pot. 1818 B. Echo.
 No wtr

Figures Indicate Bottom of Formations.

surface	0-85	Top of Arbuckle Lime 4078
sand	95	
red rock	255	Note: Above footages
red bed & sand	294	calculated from derrick
sand & shale	710	floor level, except
red bed & shale	800	formation record
shale & sand	980	
shale & red bed	1278	
shale & shells	1290	
shale	1538	
shale & shells	1675	
sand & shale	1770	
shale & shells	1875	
shale & lime	2008	
sand & lime	2100	
shale & shells	2260	
shale & lime	2669	
shale	2814	
lime & shale	2890	
lime	2945	
lime & shale	3060	
lime	3222	
lime & shale	3293	
lime	3502	
lime & shale	3544	
lime	3669	
sand	3699	
lime	3827	
lime & shale	3874	
shale	3898	
lime	3929	
lime & chert	3963	
chert	3975	
lime & chert	4000	
lime	4018	
lime, shale, sand	4038	
lime	4094	
Total Depth.		

7-17-43 drld cement out of
 7" csg-did not plug off
 hole in csg-recemented
 csg w/25 sx cement
 7-23-43 drld cement out of
 7" csg-cemented off hole
 in 7" csg
 7-26-43 deepened to 4092
 in the Arbuckle Lime
 formation - hole filled
 1500' w/oil in 30 min.
 Swbd 280 BO in 8 hrs, no
 wtr
 7-31-43 Estb. Echo. Pot.
 of 1818 BO, no wtr

7-13-43 Cemented 7" csg
 w/100 sx cement-pmpd plug
 to 406'