

KANSAS DRILLERS LOG

API No. 15 — 185 — 20,744
County Number

Operator

Continental Oil Company

Address

3535 NW 58th Street Oklahoma City, Okla

Well No.

#8

Lease Name

S. M. McCune

Footage Location

2310

feet from (N) 36 line

2080

feet from (E) 200 line

Principal Contractor

Da Dac Drilling, Inc.

Geologist

Dougherty

Spud Date

6-13-77

Total Depth

3150'

P.B.T.D.

3121'

Date Completed

7-5-77


Oil Purchaser

Skelly Oil Co.

S. 12 T. 25 R. 13 ^NW

Loc. 2310' FNL & 2080' FEL

County Stafford

640 Acres
N

Locate well correctly

Elev.: Gr. 1,916'

DF ----- KB 1925'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13 3/8"	10 3/4"	32	320'	Regular	300	3% CaCl 2% gel
Production	8 3/4"	7"	20	3150'	50-50 Pozmix	150	2% gel, 5% Gibsonite & 1/4# Flocele/sx

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
	None				
TUBING RECORD			2	1/2" Bullets	3064-72'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
6,500 gals. gel KCL water, 5,000 gals. 28% NE acid & 10,400 gals.	3064-72'
1% KCL water	

INITIAL PRODUCTION

Date of first production 7-5-77	Producing method (flowing, pumping, gas lift, etc.) Pump				
RATE OF PRODUCTION PER 24 HOURS	Oil 30 bbls.	Gas 0 MCF	Water 70 bbls.	Gas-oil ratio -----	CFPB
Disposition of gas (vented, used on lease or sold) -----			Producing interval (s) Topeka 3064-72'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Continental Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 8	Lease Name S. M. McCune		Oil
S <u>12</u> T <u>25</u> R <u>13</u> ^{EX} W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
			Logs: Laterolog Densilog Towanda 1966' Ft. Riley 2003' Indian Cave 2627' Tarkio 2749' Elmont 2809' Burlingame 2880' Howard 2956' Topeka 3050' T.D. 3150'
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Signature Marshall L. Gildermaster Engineer Title July 14, 1977 Date		