

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk Bldg., Wichita, Kansas

13-25-13W

CONTINENTAL OIL CO.
 George Russell No. 2.

SEC.13 T.25 R.13 W
 SE NE NW
 990'S 330'W of N $\frac{1}{4}$ Cor.

Total Depth. 4125' (CFL 4124)
 Comm. 6-30-42 Comp. 7-31-42
 Shot or Treated.
 Contractor.
 Issued. 10-3-42

County. Stafford



CASING:
 10 $\frac{3}{4}$ " 278' Cem.
 7" 4114' Cem.

Elevation.

Production. Echo.Pot.3000 B.

Figures Indicate Bottom of Formations. NoWtr; Ind.Cap.7312 B.

| | |
|-------------------|------|
| sand | 160 |
| red bed & shale | 290 |
| red bed | 680 |
| shale & shells | 1210 |
| salt & shale | 1320 |
| shale & shells | 1660 |
| lime brkn | 1705 |
| lime & shale | 1842 |
| lime | 1950 |
| sand & lime | 2025 |
| lime & shale | 2165 |
| lime brkn | 2365 |
| lime & shale | 2465 |
| shale | 2530 |
| shale & shells | 2825 |
| lime brkn | 2990 |
| shale & shells | 3074 |
| lime brkn | 3144 |
| lime | 3490 |
| shale & lime | 3550 |
| shale | 3613 |
| lime | 3644 |
| lime K. C. | 3681 |
| lime | 3706 |
| lime & shale | 3800 |
| lime | 3908 |
| shale & lime | 3938 |
| lime & chert | 4044 |
| lime stks & shale | 4050 |
| shale & lime | 4115 |
| lime | 4125 |

Total Depth from cement
 floor level 4124

8-3-42 Estb.Echo.Pot.3000
 BO, no wtr, Ind.Cap.7312
 bbls.

Top Arbuckle lime 4113
 Drld cement plug & hole
 filled up 1000' w/oil in
 1 hr - total fillup w/oil
 3900' - swbd 346 bbls oil
 in 4 hrs

Note: All of above
 footages are calculated
 from the cement floor
 level