

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


13-25-13W

CONTINENTAL OIL CO.  
Maggie Russell No. 1,

SEC. 13 T. 25 R. 13W  
SWc NE  
440'N 440'E Center

Total Depth. 4075'  
Comm. 1-24-39      Comp. 2-28-39      APR 22 1939  
Shot or Treated.  
Contractor.  
Issued. 4-22-39

County. Stafford



CASING:  
10 3/4"      442'  
7"      4027'

Elevation.

Production. Pot. 2843 B.

Figures Indicate Bottom of Formations.      No water

cellar	11	lime sft	3760
sand & shale	125	lime dense	3800
red bed & sand shells	350	lime	3865
red bed & shale	450	lime cherty	3870
shale & shells	545	lime	3890
red bed & shale	735	lime & shale	3912
anhydrite	755	cherty lime & shale	3978
shale & lime shells	840	cherty lime	4000
shale & shells	1275	brkn lime & shale	4024
salt	1340	lime Arbuckle	4075
salt & shale	1550	Total Depth,	
shale & lime	1625		
lime brkn & shale	1742	Top Topeka lime	3040
shale & shells	1790	Top Lansing lime	3550
lime brkn	1953	Top Viola lime	3900
lime brkn & shale	2012	Top Simpson Sand	3985
lime brkn	2040	Top Arbuckle lime	4024
sd lime	2090		
lime brkn	2105		
lime & shale	2268	Cored 4039-41 1 1/2' rec	
sd lime	2295	of cherty dolomite-fair	
lime brkn & shale	2495	porosity-spotted oil	
shale & shells	2600	shows	
lime brkn	2690	2-17-39 The cement plug was	
shale & shells	2752	drilled out and the well	
lime brkn	2770	filled up 3000' with oil	
shale & shells	2810	in 30 minutes. Fillup when	
lime brkn	2840	completed 3975'	
shale & shells	2865	3-12-39 on potential test	
lime brkn & shale	2935	the well pumped 947.65 BO	
shale & shells	2952	in 8 hrs, giving the well	
lime brkn	2976	a 24-hr potential of 2843	
shale & shells	2984	Bbls. oil, no water	
lime	3012		
shale	3037		
lime brkn	3060		
ohalky lime & shale	3105		
lime sft	3120		
lime dense white	3130		
lime brkn grey	3140		
lime	3365		

lime dense grey	3395
lime brkn	3425
lime brkn & shale	3455
shale	3512
lime & shale	3550
shale & shells	3585
lime brkn	3600
lime	3696
lime sft	3702
lime dense	3712
lime sft	3718
lime dense	3725
lime sft	3731
lime & shells	3750