


**KANSAS DRILLERS LOG**  
WICHITA BRANCH

S. 13 T. 25 R. 13 <sup>8</sup>/<sub>W</sub>

Loc. SE SW NE

County Stafford

640 Acres  
N



Locate well correctly

Elev.: Gr. 1909'

DF \_\_\_\_\_ KB 1917'

API No. 15 — 185 — 20,600  
County Number

Operator  
Continental Oil Company

Address  
3535 NW 58th Street Oklahoma City, Oklahoma

Well No. #7 Lease Name M. Russell

Footage Location  
2040 feet from (N) ~~XXX~~ line 1540 feet from (E) ~~XXX~~ line

Principal Contractor Aspen Drilling Co. Geologist Pat Curth

Spud Date 8-10-75 Total Depth 3130' P.B.T.D. 3096'

Date Completed 9-8-75 Oil Purchaser Skelly Oil Co.

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	23	329	Class H	300	2% gel, 3% Cacl
Production	8 7/8	6	18	3116	50-50 Pozmix	150	2% gel, 3/4% CFR-2

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
	None				
<b>TUBING RECORD</b>			4	Bullets	3067-72'
Size	Setting depth	Packer set at			
2 7/8"	3092'	-----			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
3000 gals. gel water pad & 5000 gals. 15% Hcl & 10% acetic acid	3067-72'

**INITIAL PRODUCTION**

Date of first production <u>8-31-75</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>40</u> bbls. Gas ----- MCF Water <u>10</u> bbls. Gas-oil ratio ----- CFPB
Disposition of gas (vented, used on lease or sold) -----	Producing interval (s) <u>3067-72'</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Continental Oil Co.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

7

Lease Name

M. Russell

Oil

S 13 T 25 S R 13 E W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Tarkio	2755
			Willard	2781
			Burlingame	2925
			Howard	2963
			Topeka	3043
			TD	3130

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



*Marshall L. Gildermeister*

Signature

Engineer

Title

9-17-75

Date

