


CONTINENTAL OIL CO.
 Marion Russell No. 2.

SEC.13 T.25 R.13 W
 NW NE SE
 350'S 990'W E $\frac{1}{4}$ Cor.

South Leesburg Unit 302

County. Stafford

Total Depth. 4408'
 Comm. 1-9-43 Comp. 2-15-43
 Shot or Treated.
 Contractor.
 Issued. 7-17-43



CASING:
 10 $\frac{3}{4}$ " 280' Cem.
 7" 4224' Cem.

Elevation.

Production. Salt Wtr Input

Figures Indicate Bottom of Formations.

| | | | |
|---------------------|------|--------------------------------------|------|
| surface clay | 0-10 | Tops: | |
| sand | 130 | Lansing-K.C. Lime | 3600 |
| red bed | 300 | Viola Lime | 3989 |
| red bed & shale | 650 | Simpson Sand | 4102 |
| shale & shells | 1290 | Arbuckle Lime | 4145 |
| salt & shale | 1385 | | |
| shale & shells | 1725 | Cored 4150-60 rec. 6 $\frac{1}{2}$ ' | |
| lime brkn & shale | 1830 | of lime- no sh oil | |
| lime | 1910 | Deepened to 4320 for | |
| lime & shale w/sand | | salt wtr input well | |
| strks | 2025 | | |
| lime w/sand strks | 2120 | 2-12-43 cleaned out to | |
| shale & lime shells | 2225 | 4224 - drld out plug | |
| shale & lime | 2295 | & cleaned hole to | |
| lime brkn | 2425 | bottom | |
| shale | 2525 | 2-13-43 deepened to | |
| shale & shells | 2690 | 4408 in sand - lost | |
| shale & lime | 2750 | circulation (Top of | |
| shale & lime shells | 2860 | Sand 4369) | |
| lime & shale | 2940 | 2-15-43 well took 90 | |
| shale & lime shells | 3015 | BWPH on test | |
| lime | 3095 | | |
| lime brkn | 3155 | | |
| lime | 3450 | | |
| lime & shale | 3475 | | |
| shale | 3550 | | |
| shale & lime | 3660 | | |
| lime | 3722 | | |
| lime sft | 3728 | | |
| lime | 3750 | lime & shale | 4125 |
| lime sft | 3773 | shale | 4140 |
| lime | 3810 | chert | 4143 |
| shale & lime | 3850 | sand & lime | 4154 |
| shale | 3875 | lime | 4231 |
| lime & shale | 3920 | lime cherty | 4235 |
| shale | 3947 | lime | 4260 |
| chert w/shale strks | 3965 | lime & shale | 4290 |
| chert & shale | 3988 | lime | 4380 |
| shale cherty | 4012 | sand | 4408 |
| chert & shale | 4045 | Total Depth. | |
| shale & lime | 4058 | | |
| shale | 4090 | | |