

13-25-13W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CONTINENTAL OIL CO.

SEC. 13 T. 25 R. 13W
LOC. APP NE NW SE

FARM Leesburg South


NO. 303

TOTAL DEPTH 4135'

COUNTY Stafford

COMM. 8-27-64

COMP. 10-1-64



SHOT OR TREATED

CONTRACTOR Red Tiger Drlg.

ISSUED 12-10-66

CASING

20	10	
15	8 5/8	321' w/150 sx cem.
12	6	
13	5 1/2	4134' w/200 sx cem.

ELEVATION 1918' KB

PRODUCTION INJECTION
WELL-RATE SATISFACTORY

FIGURES INDICATE BOTTOM OF FORMATIONS (LANS & SIMP 3720-4087)

COMPLETE DRILLERS LOG NOT AVAILABLE.

TOPS: SCOUT	
Topeka	3060
Queen Hill	3279
Heebner	3399
Lansing	3575
Viola	3993
Simpson	4065
Arbuckle	4111

13-25-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CONTINENTAL OIL CO.
Farm- Marion Russell No. 3

SEC. 13 T. 25 R. 13W
NE NW SE
2365' FSL 1680' FEL

Total Depth. 4135'
Comm. 8-27-64 Comp. 9-7-64
Shot or Treated.
Contractor. Red Tiger Drlg. Co.
Issued. 10-31-64

County Stafford
KANSAS



Elevation. 1920' K.B.

CASING:

8 5/8" 321.42' w/150 sx cem.
5 1/2" 4134' w/200 sx cem.

Production. Input.

Figures indicate Bottom of Formations.

sod, sand 110
red bed, shale 745
anhydrite 760
shale, shells 1620
shale, lime 3535
lime 3935
lime, chert 4040
chert 4086
lime 4135
Total Depth

TOPS: SGOUT

*Topeka 3061
Queen Hill 3278
Heebner 3399
Lansing 3579
B/Kansas City 3807
Viola 3968
Simpson 4065
Arbuckle 4117
* Sample top.