

30-25-13W

County Stafford  
 KANSAS

Total Depth. 4365  
 Comm. 6-22-55 Comp. 7-10-55  
 Shot or Treated.  
 Contractor.  
 Issued. 12-24-55



CASING:

8 5/8 332' w/ 200 sx cmt.  
 5 1/2 4364' w/ 150 sx cmt.

Elevation. 1959 RB

Production. 164 BOPD

Figures indicate Bottom of Formations

|                      |      |
|----------------------|------|
| sand & shale         | 270  |
| red bed & shale      | 870  |
| anhydrite            | 890  |
| shale & shells       | 1200 |
| sand, shale & shells | 1565 |
| shale & shells       | 1850 |
| shale & lime         | 3135 |
| shale                | 3280 |
| shale & lime         | 3509 |
| shale                | 3585 |
| sandy lime & shale   | 3690 |
| lime                 | 3966 |
| shale & lime         | 4091 |
| shale                | 4160 |
| chert                | 4203 |
| lime & chert         | 4262 |
| lime & shale         | 4288 |
| lime & sand          | 4297 |
| sand & shale         | 4345 |
| lime                 | 4365 |
| Total Depth          |      |

SCOUT TOPS:

|               |      |
|---------------|------|
| Heebner       | 3526 |
| Brown lime    | 3682 |
| Lansing       | 3708 |
| Mississippi   | 4080 |
| Kinderhook    | 4105 |
| Viola         | 4159 |
| Simpson shale | 4281 |
| Simpson sand  | 4289 |
| Arbuckle      | 4345 |

DST #1: 3848-80, open 1 hr. SI 7 min.  
 rec. 640' clean oil, 360' foggy oil,  
 no water, IFP 110#, FFP 300#, BHP  
 1160#/20 min.

DST #2: 3885-3905, open 1 hr. wk. bl.  
 15 min. rec. 25' WD & trace oil,  
 BHP 0#

DST #3: 4168-4203, open 1 hr. SI 20  
 min. rec. 75' SOCM, no wtr., IFP 12#,  
 FFP 25#, BHP 385#

DST #4: 4280-97, open 1 1/2 hrs. SI 20  
 min. rec. 200' oil, 60' HO&GCM, IFP  
 0#, FFP 60#, BHP 550#.

Ran Schlumberger E. L.