

1-25-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- WENTWORTH & SONS
Farm- J. E. Sanders No. 1

SEC. 1 T. 25 R. 14W
SE SE NW

Total Depth. 4376
Comm. 7-27-54
Shot or Treated.
Contractor.
Issued. 10-2-54

Comp. 8-16-54

County Stafford
KANSAS



CASING:

8 5/8 275'

Elevation. 1955 KB

Production. Dry

Figures Indicate Bottom of Formations.

soil, sand & shale	185
shale, & lime shells	275
lime shells, shale & red bed	870
anhydrite	890
shale & shells	1735
lime & shale	2395
lime, shale & sand	2730
shale & shells	3015
lime & shale	3255
lime	3545
lime & shale	3716
lime	4006
shale & lime	4010
cherty lime	4060
shale & lime	4124
chert, cherty lime & shale	4300
shale & lime	4322
shale, lime & sand	4348
dolomite	4376
Total Depth	

DST #3: 4124-85, open 1 hr. rec. 30'
faintly oil specked gassy mud, 60'
thin gassy mud, 120' muddy water,
IFP 60#, FFP 135#, BHP 1200#

DST #4: 4220-83, open 1 hr. rec. 5'
sl. oil specked & GCM, 120' oil specked
& WCM, 60' muddy water, IFP 70#,
FFP 125#, BHP 795#

DST #5: 4312-22, open 1 hr. rec. 60'
sl. oil specked watery mud, BHP 1317#

TOPS:	
Topeka	3210
Heebner	3524
Toronto	3540
Brown lime	3667
Lansing-KC	3697
Conglomerate	4009
Mississippi lime	4020
Kinderhook	4040
Viola lime	4113
Simpson shale	4296
Arbuckle	4348

DST #1: 3920-50, open 1 hr. rec. 30'
SO specked & SWCM, IFP 30#, FFP 50#,
BHP 955#

DST #2: 4103-24, open 1 hr. rec. 90'
SO&GCM, IFP 45#, BHP 250#