

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


1-25-14W

Company- MUSGROVE PETROLEUM CORP.
Farm- Sanders No. 2

SEC. 1 T. 25 R. 14W
C NW NE NW

Total Depth. 4315'
Comm. 4-11-58 Comp. 4-23-58
Shot or Treated.
Contractor. Musgrove Petr.
Issued. 8-9-58

County Stafford
KANSAS



Elevation. 1954' DF

Production. 823 BOPD, NW

CASING:

8 5/8" 317' cem w/275 sx.
5 1/2" 4136' cem w/200 sx.

Figures Indicate Bottom of Formations.

top soil, sand & shale	320
red bed	375
shale, sand & shells	1200
red bed, sand & lime shells	1750
lime & shale	3720
lime	3788
lime & shale	3806
lime	4050
chert & shale	4105
lime & chert	4149
lime, shale & chert	4193
lime	4236
lime, shale, chert	4276
lime & shale	4302
lime	4315 RTD
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Heebner	3493	3493
Lansing	3666	3662
Base Kansas City	3945	3942
Mississippi	4010	4010
Kinderhook	4054	4052
Viola	4115	4118
Simpson	4251	4245
Simpson Sand	4261	4262
Arbuckle	4304	