

2-25-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **AYLWARD DRILLING CO. ET AL**
 Farm- **Bowker "A"** No. **1**

SEC. **2** T. **25** R. **14W**
 C **E/2** SE NE

Total Depth. **4318'**
 Comm. **6-20-59** Comp. **7-3-59**
 Shot or Treated.
 Contractor. **Aylward Drlg. Co.**
 Issued. **10-3-59**

County **Stafford**
KANSAS



CASING:
8 5/8" 240' cem w/200 sx.

Elevation. **1958' RB**

Production. **Dry**

Figures Indicate Bottom of Formations.

sand	140
shale	240
red bed	450
sand & red bed	600
red bed	890
Anhydrite	910
shale & shells	1356
shale - lime strks	1580
shale & shells w/lime	
streaks	1720
lime & shale	1820
lime	1945
lime w/shale	2068
lime & shale	2200
shale w/lime strks	2285
lime & shale	2396
shale & lime	2825
shale w/lime	2965
shale & lime	3165
lime	3205
chalky lime & shale	3285
lime	3510
lime & shale	3635
lime	3994
lime & shale	4060
lime	4103
lime & shale	4108
shale	4167
chert & shale	4175
cherty shale	4214
lime - cherty	4232
shale & lime	4307
lime	4318
Total Depth	

Viola	4164
Simpson	4252
Arbuckle	4300

DST 4022-4103', op 1 hr., rec. 2468' GCMSW
 IBHP 1320#/20" - FBHP 1270#/30", FP 670#-
 1230#.

TOPS:

Heebner	3517
Toronto	3540
Douglas	3560
Brown Lime	3660
Lansing	3686
Mississippian	4062
Kinderhook	4102