

4-25-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Farm- Spencer No. 1

SEC. 4 T. 25 R14W
NW SW SE

Total Depth. 4201'
Comm. 12-15-60 Comp. 12-27-60
Shot or Treated.
Contractor.
Issued. 4-15-61

County Stafford
KANSAS



Elevation. 1986' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	15
sand	110
shale	273
red bed	560
red bed & sand	580
red bed & shale	810
Anhydrite stringers	930
shale & shells	1650
shale & lime	1805
lime	1888
lime & shale, shells	1949
lime w/shale & clay	1980
shale & lime	2175
lime	2210
shale & lime	2260
lime	2355
lime & shale	2395
shale & lime	2550
shale w/lime	2730
shale & lime	2895
lime & shale	3290
shale & lime	3400
lime & shale	3424
shale & sand	3465
lime & shale	3620
lime	4160
lime w/shale & chert	4201
Total Depth	

DST 4113-31', op 1 hr, rec. 50' S1 GCM
w/few specks oil. 420' gas in pipe.
IBHP 180#/20 min, FBHP 95#/30 min,
FP 0-0#

Perf. from 4113 to 4140, 3 shots per ft.
Acidized. 1000 mud acid.
Frac. w/10,000 oil & 10,000# sand

TOPS:

Heebner	3557
Toronto	3581
Douglas	3599
Brown Lime	3701
Lansing	3727
Base Kansas City	3995
Mississippian	4112
Kinderhook	4173

DST 3860-3933', op 1 hr, rec. 1200' SW,
IBHP 1120#/20", FBHP 1115#/30", FP 110-480#.