

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

8-25-14W

Company- APACHE OIL CORP.
 Farm- Bear No. 1

SEC. 8 T. 25 R. 14W
 NW NW SW

Total Depth. 4435'

Comm. 6-13-56


Comp. 6-27-56

Shot or Treated.

Contractor. Welch & Olsson Drlg.

Issued. 10-13-56

County Stafford
 KANSAS



Elevation. 1993' RB

CASING:

8 5/8" 239.79' w/200 sx cem
 5" 4265'

Production. 10 BOPD

Figures indicate Bottom of Formations.

Red bed & shale	425
sand	460
red bed & shale	910
Anhydrite	930
shale & shells	1825
lime & shale	3750
lime	4160
shale	4215
Chert -	4222
lime	4291
lime & chert	4325
sand	4404
lime	4435

Total Depth

TOPS:

Anhydrite	910
Heebner	3573
Toronto	3591
Douglas	3609
Lansing	3740
Base/Kansas City	4004
Conglomerate	4127
Kinderhook	4155
Mississippi Ch	4170
Viola	4256
Simpson Shale	4347
Simpson Dolomite	4364
Arbuckle	4402