


Company- CITIES SERVICE OIL COMPANY
Farm- Hammond No. 2

SEC. 9 T. 25 R. 14W
SW SE SW
330' N. & 990' W of
S/4 Cor.
County Stafford
KANSAS

Total Depth. 4035'
Comm. 11-20-57 Comp. 12-6-57
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 2-22-58



CASING:

8 5/8" 409' cem w/275 sx

Elevation. 1982 (1979) Gr.

Production. Dry

Figures indicate Bottom of Formations.

sand	150
shale	320
red bed	410
red bed, shale & shells	810
red bed	895
anhydrite	920
red bed	1280
shale	1580
lime & shale	1975
lime	2170
lime & shale	2410
lime	2500
shale & shells	2550
lime & shale	2675
lime, shale & shells	2945
lime & shale	3135
lime	3275
lime & shale	3368
lime	3813
lime, cherty	3860
lime	4035
Total Depth	

TOPS:

Topeka	3137
Heebner	3559
Dodge	3580
Douglas	3601
Brown limestone	3706
Lansing	3730
Base Kansas City	4019

DST 3772-3813, open 1 hr., rec. 240' muddy salt water & 455' salt water; BHP 1210#/30 min.

DST 3861-77, open 1 hr, rec. 35' slightly oil-spotted mud & 5' muddy water; BHP 790#/30 min.

DST 3879-3908, open 1 hr, rec. 39' mud; BHP 1142#/30 min.

DST 3909-27, open 1 hr, rec. 90' muddy salt water; BHP 1278#/30 min.

DST 3939-54, open 1 hr., rec. 5' oily mud, 30' watery mud with show oil, & 65' muddy salt water; BHP 1020#/30 min.