

9-25-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. COOPERATIVE REFINERY ASS'N.
Farm. Hammond "C" No. 1

SEC. 9 T. 25 R. 14W
SE NE SW

Total Depth. 4355'
Comm. 4-26-57 Comp. 5-20-57
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 8-31-57

County Stafford
KANSAS



CASING:
8 5/8" 288' cem w/250 sx.
5 1/2" 4013' cem w/100 sx.

Elevation. 1972' DF

Production. 282 BOPD

Figures indicate Bottom of Formations.

sand and clay	40
shale	295
red rock	892
gypie lime	924
gray shale and red rock	1050
shale	1275
shale and lime strks	1360
shale	1572
red rock	1610
lime	1670
red rock	1770
lime	2032
lime and shale	2283
lime	2400
lime and shale	2548
lime	2630
lime and shale	3176
lime	3205
gray shale	3210
lime and shale	3235
lime	3370
lime, sandy	3394
lime and black shale	3431
lime	3595
gray shale & red rock	3643
brown lime & gray shale	3667
shale	3710
shale and lime	3756
lime	4020
lime and shale	4060
lime	4096
chert	4112
lime-chert	4132
shale-brown	4141
lime and shale	4243
lime	4270
lime and chert	4296
shale	4345
Arbuckle lime	4355 RTD
Total Depth	
TOPS: SCOUT	
Heebner	3537
Toronto	3556

Douglas	3575
Brown Lime	3678
Lansing	3708
Mississippi Chert	4087
Viola	4162
Simpson Shale	4298
Simpson Sand	4308
Arbuckle	4346