


11-25-14W

County Stafford
KANSAS



Total Depth. 4290 PB 4177
Comm. 8-9-53 Comp. 10-9-53
Shot or Treated.
Contractor.
Issued. 4-2-55

CASING:

8" 870' cem w/500 sx
5" 4321' cem w/250 sx

Elevation. 1959

Production. 3 BO / 13 BW/24 hrs

Figures indicate Bottom of Formations.

sand, shale	483
red bed, lime	860
anhydrite	888
sand, shale	1307
shale, lime	2048
sand, shale	2306
shale	2820
lime, shale	3389
lime	3473
lime, shale	3813
lime, chert	3891
lime	3931
lime, shale	3989
lime, chert, shale	4061
chert	4086
shale, lime	4121
lime, chert	4272
lime	4290 RTD
Total Depth	P. B. 4177

from 9-11 to 10-9 when state pot.
was taken.

Tops:

Heebner	3510
Toronto	3529
Douglas	3547
Brown Limestone	3646
Lansing-K. C.	3677
Base L.K. C.	3958
Marmaton	3972
Mississippian	4042
Kinderhook shale	4051
Viola	4115
Crystalline Viola	4247
Simpson shale	4275

OTD 4290, 5" 4231', Drlg out
cement PBD 4181, Perf. 56
4148-62, Bailed 1.52 BO &
1.80 BW in 1 1/2 hrs. Acid 4148-
62 w/3000 gals. Swb 18.08 BO
& 52.84 BW in 7 hrs. Baker plug
at 4144. Perf. 5" csg 4130-41
w/44 shots. Last Hour 1 BO &
1/2 BW, acid w/500 & 3000 gals.
test 1 BO & 1/2 BW approx.
Drove plug from 4144 to 4179
Perf. 7" csg 4115-25 w/40 shots
& acid w/2500 4115-25. Last
hr 1/2 BO approx. & 1 1/4 BW.
Drove plug 4127-4177, test approx.
1 BO & 1 BW per hr. Was pumped