

12-25-14W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- PETROLEUM, INC.
 Farm- Bowker "B" No. 2

SEC. 12 T. 25 R. 14W
 SW NE NW

Total Depth. 4320'
 Comm. 9-28-59 Comp. 10-11-59
 Shot or Treated.
 Contractor. Garvey Drlg.
 Issued. 12-26-59

County Stafford
 KANSAS



CASING:

8 5/8" 270' cem w/200 sx.
 4 1/2" 4218' cem w/350 sx.

Elevation. 1957' DF

Production. 220 BOPD

Figures Indicate Bottom of Formations.

sand & clay	159
clay & shale	270
red bed & shale	855
Anhydrite	885
shale & shells	1530
shale & lime	1905
lime	2247
lime & shale	2360
shale & lime	3290
lime & shale	3537
lime & sand	3633
lime & shale	3722
lime	3950
lime & shale	3979
lime	4034
chert	4050
cherty lime	4052
shale	4100
cherty lime	4150
lime & chert	4250
shale	4311
Arbuckle	4320
Total Depth	

TOPS: SCOUT

Hecbner	3501
Douglas	3537
Brown Lime	3635
Lansing	3664
Base Kansas City	3946
Conglomerate	3985
Mississippi	4017
Kinderhook	4034
Viola	4099
Dolomite	4105
Simpson Shale	4247
Simpson Sand	4264
Arbuckle	4301