

13-25-14W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **ASPEN DRIG. & DEAN & CLARK**

SEC. 13 T. 25 R. 14W
 LOC. NW NW SE

FARM **Kackleman** NO. 1

TOTAL DEPTH **4351**
 COMM. **10-30-66** COMP. **11-9-66**
 SHOT OR TREATED
 CONTRACTOR **Aspen Drlg.**
 ISSUED **1-14-67**

COUNTY **Stafford**
 KANSAS



CASING

20	10	
15	8 5/8"	@ 242' w/225 SX
12	6	
13	5	

ELEVATION **1971'KB**

PRODUCTION **DRY (Arb)**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand-Shale	245
Red Bed	852
Anhydrite	870
Shale & Shells	1250
Lime & Shale	1930
Lime	2110
Shale & Lime	2595
Lime & Shale	3515
Lime	3905
Chert, Lime & Shale	4210
Lime, Chert (Viola)	4264
Simpson	4295
Lime	4330
Lime (Arbuckle)	4351

Surface pipe set at 11:00 PM
 10-30-66. Ran 12 jts. (235')
 8 5/8" O.D. used casing. Set
 at 242', cemented with 225 sax
 Sunset. Cement circulated.

DST#1 57' anchor
 DST#2 81' anchor

Ran Radiation Accrulog

TOPS: SCOUT

Heebner	3538
Toronto	3559
Douglas	3578
Brown Lime	3694
Lansing	3725
Base Kansas City	4012
Mississippi Chert	4076
Viola	4147
Simpson Sand	4277
Arbuckle	4323

SAMPLE TOPS

Heebner	3543
Brown L,	3697
Lansing	3727
Base KC	4016
Miss.	4088
Viola	4148
Simpson Sd.	4276
Arbuckle	4326

AFFIDAVIT

STATE OF KANSAS)
) SS:
 COUNTY OF BARTON)

The undersigned, being duly sworn on oath, states that the above