


13-25-14W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KERN DRILLING CO., INC. & HELLAR DRIG. CO., SEC. 13 T. 25 R. 14W
Farm- Kachelman No. 1 INC. SW NW NE

Total Depth. 4270'
Comm. 10-11-65 Comp. 10-23-65
Shot or Treated.
Contractor. Hellar Drig. Co., Inc.
Issued 2-5-66

County Stafford
KANSAS



CASING:
8 5/8" 242' w/225 sx com.
4 1/2" 4269' w/250 sx com.

Elevation. 1966; KB

Production. Pmp. 76 BOPD, NW

Figures indicate Bottom of Formations.

sand	160
shale	242
shale, red bed, sand	850
Anhydrite	867
red bed, shale	1304
salt section	1922
lime, shale	2035
Ft. Riley (Cherty lime)	2200
shale, lime	3184
lime, chalky	3360
brkn lime	3473
shale, lime	3715
lime	3778
Kansas City lime	3848
lime	3929
lime, shale	4095
lime	4102
Viola chert	4214
Simpson sand	4229
shale, lime	4254
Arbuckle	4270
Rotary Total Depth	

TOPS: SCOUT

* Anhydrite	250-67
Topeka	3086
Heebner	3504
Brown lime	3660
Lansing	3691
* B/Kansas City	3973
* Mississippi	4073
Viola	4128
Simpson shale	4198
Simpson sand	4214
Arbuckle	4270

* Sample tops.