


EMPIRE O. R. CO.
Stimatze No. 1.

SEC. 15 T. 25 R. 14W
NWc SW 15-25-14W
330' S 330' E of W/4 Cor.

Total Depth. 3809'
Comm. 5-17-37 Comp. 6-15-37
Shot or Treated. 4000 Gals.
Contractor. Corbett & Barbour
Issued. 8-7-37

County. Stafford

AUG 7 1937



L. Novacek.
Plotted

CASING:
12 1/2" 309'
7 " 3781' SLM

Elevation. 1970

Production. Pot. 1088 B.
flow 23 hrs.

Figures Indicate Bottom of Formations.

sand & red beds	225	lime cored	3795
red beds & shells	309	lime sft	3802
shale & shells	404	SLM Corr. 3802=3795	
brkn lime	423	lime sft	3809
shale	500	Total Depth.	
brkn lime	517		
shale & shells	800	Top K.C. 3605	
salt & shale	950	Pen 204	
shale	1037	T.D. 3809	
shale & shells	1149		
shale	1290		
brkn lime	1323		
shale & shells	1500		
brkn lime	1540		
shale	1708		
brkn lime	1844		
lime	2090		
shale	2117		
shale & shells	2175		
lime	2270		
shale & shells	2313		
brkn lime	2527		
shale	2558		
lime brkn	2583		
shale & lime shells	2710		
lime	2742		
shale & lime shells	2843		
shale & brkn lime	2903		
brkn lime	2945		
shale & brkn lime	3043		
brkn lime	3060		
lime	3133		
brkn lime	3150		
lime	3433		
lime hrd	3450		
brkn lime	3510		
shale & lime shells	3628		
lime	3630		
shale(cored)	3632		
lime cored	3640		
S.S.G 3633-35			
lime	3692		
show oil 3692-3701			
lime brkn	3710		
lime	3754		
brkn lime	3765		
lime	3780		