

CITIES SERVICE OIL CO.-ATLANTIC REFG.CO.

Stimatze No. 2

SEC. 15 T. 25 R. 14W.

CEL NW SW

660' S. 990' E of W $\frac{1}{2}$ corner.

Total Depth. 3802

Comm. 2-13-41 Comp. 3-2-41

Shot or Treated. 5000 gal. March 4, 1941

Contractor. Hissom Drilling Co.

Issued. 5-24-41

County Stafford.



CASING.

85/8" 377' cemented.

5 1/2" 3773' cemented.

Elevation.

Production. Pot. 2910 B.O.

90 BW.

Figures Indicate Bottom of Formations.

sand	160
shale and shells	210
red bed and shells	377
red bed and shale	800
shale and lime shells	1025
shale and shells	1050
anhydrite	1090
shale and red bed	1200
shale and salt	1458
shale and shells	1785
lime	2462
shale and lime broken	2580
broken lime	2665
lime	2737
lime and shale	2835
broken lime	2923
lime and shale	3083
broken lime and shale	3185
lime	3550
shale	3603
lime	3794
3794 Rot.T.D. equals 3794 SLM	
lime	3802

Total Depth.

B.H.P.Gauge Potential: 2910 Oil, 90 water, 24 hours.

(Fluid capacity 4238 bbls., 3% water.)

Top Lansing	3613
Penetration	189'