

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-25-14W

Company- CITIES SERVICE OIL CO., et al.
 Farm- Stimatze No. 3

SEC. 15 T. 25 R. 14W
 NW SW SW
 990' N & 330' E SWc

Total Depth. 3910 SLM 3906 PBSD 3761
 Comm. 8-17-52 Comp. 8-29-52
 Shot or Treated.
 Contractor. Barbour Drilling Co.
 Issued. 1-10-53

County Stafford
 KANSAS



CASING:

8 5/8 406 w/ 250 sx cement
 5 1/2 3906 w/ 150 sx cement

Elevation. 1978

Production. 95 BO 40 BW 24 hrs.

Figures Indicate Bottom of Formations.

clay & sand	130		TOPS CORR.
shale	180		
red bed	315	Heebner	3468
sand	355	Brown lime	3611
red bed	410	Lansing	3640
red bed & shells	565		
red bed	825		
anhydrite	845		
shale & shells	1800		
lime & shale	2520		
shale	2930		
shale & lime	3370		
lime	3450		
lime & shale	3600		
lime	3910	R. T. D. SLM 3906	

Acidized 2000 gals. 3848-3873

Perforated 34 shots 3858-3867 32 shots 3848-3856

Acidized 2000 gals. 3848-3867

Perforated 34 shots 3779-3788 6 gal oil per hr.

Acidized 1000 gals. 3779-3788

Perforated 41 shots 3716-3726

Acidized 1000 gals 3716-3726