

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-25-14W

CITIES SERVICE OIL CO. &

Company- ATLANTIC REFINING CO.

Farm- Stimatze

No. 4


SEC. 15 T. 25 R. 14W

C NW NE SW

330' S & 990' W of

Center

County Stafford
KANSAS



1970' DF

Elevation. _____

Production. 95 oil, 10 wtr.,
24 hrs.

Total Depth. 3900' PBD 3885'
Comm. 9-28-56 Comp. 10-13-56
Shot or ~~Washed~~ 8000 gals. 10-19-56
Contractor. Prime Drilling Company
Issued. 12-1-56

CASING:

8 5/8" @408' w/250 sx cem.
5 1/2" @3900' w/150 sx cem.

Figures Indicate Bottom of Formations.

sand & gravel	202
shale & shells	295
red bed	850
Anhydrite	875
shale & shells	1600
lime & shale	1845
lime	2005
sandy lime	2020
lime	2035
lime & shale	3040
lime	3515
lime & shale	3630
lime SIM	3900 RTD
Total Depth	

GEOLOGICAL TOPS

Topeka	3042
Heebner	3457
✓Dodge	3477
Douglas Sand	3531
Brown Limestone	3601
Lansing	3627
Penetration	273

Drilled cement to 3885 SIM

PERFORATING RECORD

41 shots 3858-68
17 shots 3852-56
73 shots 3806-24
37 shots 3791-3800
33 shots 3768-76
37 shots 3712-21
9 shots 3708-10
17 shots 3702-06

10-19-56 ACIDIZING RECORD

2000 gals. 3852-68
2000 gals. 3806-24
1000 gals. 3791-3800
1000 ga ls. 3768-76
2000 gals. 3702-21