


Total Depth. 3836'  
Comm. 4-1-37 Comp. 5-2-37  
Shot or Treated. 4000 Gals.  
Contractor. Corbett & Barbour  
Issued. 5-29-37



*A. Wheeler*  
*Plotted*

CASING:

121/2"      293'  
65/8"      3803'

Elevation.

Production. Pot. 3366 B.

Figures Indicate Bottom of Formations. No wtr, after acid.

|                        |         |                            |
|------------------------|---------|----------------------------|
| sand & clay            | 160     | Flowed by heads for 5 hrs. |
| red bed                | 241     | Est. 25 bbls. per hour.    |
| red bed & shale        |         |                            |
| blue                   | 265     |                            |
| shale & shells         | 293     |                            |
| shale & sand           | 320     |                            |
| shale & shells         | 1000    |                            |
| shells                 | 1020    |                            |
| shale                  | 1080    |                            |
| lime shells & shale    | 1252    |                            |
| shale & shells         | 1670    |                            |
| brkn lime              | 1807    |                            |
| lime                   | 1933    |                            |
| brkn lime              | 2229    |                            |
| lime                   | 2297    |                            |
| brkn lime              | 2397    |                            |
| lime                   | 2435    |                            |
| shale                  | 2454    |                            |
| shale & lime           | 2628    |                            |
| lime brkn              | 2638    |                            |
| shale                  | 2703    |                            |
| shale & shells         | 2784    |                            |
| shale                  | 2867    |                            |
| shale & shells         | 2930    |                            |
| lime brkn              | 2991    |                            |
| brkn lime              | 3004    |                            |
| shale                  | 3020    |                            |
| lime                   | 3125    |                            |
| brkn lime              | 3174    |                            |
| shale & lime           | 3240    |                            |
| brkn lime              | 3326    |                            |
| lime & chert           | 3359    |                            |
| lime & shells          | 3365    |                            |
| lime                   | 3465    |                            |
| brkn lime              | 3520    |                            |
| shale                  | 3568    |                            |
| brkn shale             | 3602    |                            |
| shale & lime           | 3615    |                            |
| lime                   | 3660    |                            |
| SLM Corr 3660          | =3710   |                            |
| lime                   | 3712    |                            |
| lime                   | 3720    |                            |
| S.O. & G.              | 3712-20 |                            |
| lime (cored)           | 3740    |                            |
| lime                   | 3782    |                            |
| lime (cored)           | 3792    |                            |
| (O. & G. sat. 3782-92) |         |                            |
| lime                   | 3815    |                            |

(S.O. 3786-3800)  
lime hrd                      3822  
lime sft (more Oil) 3836  
Total Depth.  
  
Top Lansing - K.C. 3640  
Penetration                196'  
Total Depth.                3836'

