

16-25-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

CITIES SERVICE OIL CO. &
Company. ATLANTIC REFINING CO.
Farm. Neeland "B" No. 4

SEC. 16 T. 25 R. 14W
NE SW SE
990' N & 990' E of S4c

Total Depth. 3915
Comm. 8-30-55 Comp. 9-12-55
Shot or Treated.
Contractor. Barbour Drilling Co.
Issued. 11-12-55

County Stafford
KANSAS



8 5/8 @ CASING:
387' w/ 350 sx cmt.

Elevation. 1971

Production. Dry

Figures indicate Bottom of Formations.

sand	175
red bed	225
red bed & shale	387
red bed	824
anhydrite	842
shale & shells	1595
lime & shale	2500
shale	2660
lime & shale	3412
lime	3480
lime & shale	3625
lime	3655
lime & shale	3715
lime	3915
Total Depth	

TOPS:
Heebner 3484
Brown lime 3624
Lansing 3651
Penetration 264

DST #1: 3723-42, open 1 hr. rec. 10'
sl. oil spotted mud, 80' mud, 60'
muddy SW, BHP 610#/30 min.

DST #2: 3741-76, open 1 hr. rec. 195'
muddy SW, BHP 1090#/30 min.

DST #3: 3775-91, open 30 min. rec.
15' muddy SW, BHP 1192#/30 min.

DST #4: 3791-3840, open 1 hr. gas in
1 hr. rec. 15' SOCM, 180' HGC&SOCM,
BHP 375#/30 min.

DST #5: 3698-3714, straddle packer
open 1 hr. rec. 60' GC&SOCM, BHP
400#/30 min.

DST #6: 3840-64, open 1 hr. rec. 115'