

18-25-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.
Farm- Foley No. 1

SEC. 18 T. 25 R.14W
SE NE SE

Total Depth. 4460'
Comm. 2-15-61 Comp. 3-1-61
Shot or Treated.
Contractor. Garvey Drilg. Co.
Issued. 9-9-61

County Stafford
KANSAS



Elevation. 1985' DF

Production. 94 BOPD/Viola
47 BOPD/Kansas City

CASING:

8 5/8" 291' cem w/275 sx.
5 1/2" 4356.11' cem w/250 sx.

Figures Indicate Bottom of Formations.

| | |
|-----------------------|------|
| surface sand & gravel | 187 |
| gravel & red bed | 225 |
| red bed & gyp | 291 |
| red bed | 600 |
| red bed & shells | 1220 |
| shale & lime | 1700 |
| lime & shale | 1800 |
| lime | 1945 |
| lime & shale | 2135 |
| lime | 2235 |
| lime & shale | 2605 |
| shale & lime | 2790 |
| shale | 2990 |
| shale & lime | 3370 |
| lime & shale | 3480 |
| lime | 3560 |
| lime & shale | 3630 |
| shale | 3700 |
| lime | 4030 |
| lime & shale | 4109 |
| lime | 4130 |
| chert | 4154 |
| shale | 4168 |
| lime & shale | 4237 |
| chert & lime | 4280 |
| lime | 4322 |
| chert & lime | 4367 |
| lime | 4460 |
| Total Depth | |

TOPS: SCOUT

| | |
|-------------------|------|
| Heebner | 3561 |
| Toronto | 3579 |
| Douglas | 3601 |
| Brown Lime | 3700 |
| Lansing | 3727 |
| Base Kansas City | 4027 |
| Mississippi Chert | 4127 |
| Kinderhook | 4144 |
| Viola | 4214 |
| Simpson Shale | 4383 |
| Arbuckle | 4388 |