

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


19-25-14W

Company- WESTERN PETROLEUM COMPANY, INC.
Farm- Boylan No. 1

SEC. 19 T. 25 R. 14W
C NE SW

Total Depth. 4350'
Comm. 8-7-63 Comp. 8-18-63
Shot or Treated.
Contractor. Western Petroleum
Issued. 11-30-63

County Stafford
KANSAS



CASING:

Elevation. 1991' DF

8 5/8" 317' wem w/ 300 sx

Production. Dry

Figures Indicate Bottom of Formations.

soil, sand shells	260
red bed & shells	318
red bed	922
anhydrite	940
red bed, shale, shells	1245
shale & shells	1715
shale, shells, red bed	2065
shale & lime	2215
lime & shale	2455
shale & lime	2570
lime & shale	2674
shale & lime	2799
lime & shale	2939
shale & lime	3155
lime & shale	3283
shale & lime	3410
lime & shale	3460
lime	3607
lime & shale	3755
lime	4208
chert	4225
lime & shale	4260
shale	4276
chert	4303
chert & lime	4332
lime	4350 RTD
Total Depth	

TOPS: LOG

Anhydrite	934
Hoebner	3606
Lansing	3378
Base Kansas City	4060
Mississippi	4216
Kinderhook	4225
Viola	4277

DST # 1 4187-4225' Op 40 min. Weak blow
for 9 min. Rec. 12' drilling mud. No
shows. IBHF 0# 30 min; FBHF 0# 30 min;
IFP-FFP 0#; HM 2015#.