

23-25-14W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company CITIES SERVICE OIL CO.  
Farm Kipp No. 1

SEC. 23 T. 25 R. 14 W  
NEc NE  
330' S & 380' W of NE Cor.

Total Depth. 4303' PB 3961'  
Comm. 4-8-46 Comp. 5-2-46  
Shot or Treated. 2000 gals. acid 5-10-46  
Contractor. Holm Drlg. Co.  
Issued. 6-29-46

County. Stafford  
KANSAS



Elevation. 1968

Production. B.H.P. Gauge Pot.  
1260 Oil, no wtr.

CASING:

10 3/4" 395' Cem.  
5 1/2" 3973' Cem.

Figures Indicate Bottom of Formations.

sandy clay	0-40
sand & gravel	190
shale & shells	585
shale red	685
sand red	800
shale sdy red	845
lime	880
shale red	900
shale & shells	910
shale red	1040
shale & shells	1165
shale	1300
salt & shale	1585
lime & shale	1700
lime & shale brks	1875
gyp & lime	2000
lime & shale brks	2210
lime & shale	2300
lime & shale brks	2400
lime & shale	2575
lime & shale brks	2695
lime & shale	3275
lime	3445
lime & shale brks	3500
lime	3575
shale & lime	3625
lime & shale brks	3665
lime	4084
lime cherty	4103
shale	4149
lime & chert	4154
lime	4173
lime & chert	4211
lime	4215
lime & chert	4217
sand	4232
sand & shale	4237
shale	4264
lime	4303
Total Depth. PB 3961'	

Tops:

Lansing (Corr) 3654  
Arbuckle 4257  
Penetration 46'

Drilled cement to 3961' SIM

Perf. 24 shots 3844-49'  
Perf. 58 shots 3852-63

825' oil in hr.  
2200' oil in 3 hrs.  
Hole full oil & flowing in 8 hrs.