


SKELLY OIL CO.
Emma J. Kipp No. 1.

23-25-14W
SEC. 23 T. 25 R. 14W
SWc SE
440' fr SL 440' fr WL SE $\frac{1}{4}$

Total Depth. 3811'
Comm. 8-19-37 Comp. 9-10-37
Shot or Treated.
Contractor. Bodine Drlg. Co.
Issued. 10-23-37 Rotary O-3811'

County. Stafford

OCT 23 1937



CASING:
13" 849'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand & gravel	226
red rock	400
lime	440
red rock	795
lime & red rock	825
lime & anhydrite	860
shale	879
red rock	940
lime	950
red rock	1130
shale sft	1380
shells sft	1490
red & grey shale	1640
salt sft	1700
shale sft	1750
lime hrd	1810
shale sft	1830
lime hrd	2045
shale sft	2060
lime brkn hrd	2120
lime hrd	2140
shale sft	2170
lime hrd	2200
lime brkn	2265
lime hrd	2630
lime brkn	2645
lime hrd	2770
lime hrd & chert	2785
limo	2845
shale hrd	2950
limo	3060
shale hrd	3080
lime hrd	3090
shale sft	3190
lime hrd	3205
shale red & grey	3285
lime hrd	3360
shale sft	3400
lime hrd	3445
shale sft	3485
lime hrd	3535
Base Mt Oread limo	3520
shale	3540
lime	3560
shale red & grey	3565
lime	3630

Bottom Mt Oread lime 3520
Top Lansing lime 3750
No shows gas or oil.

shale	3695
SL Corr. 3695-3697 $\frac{1}{2}$	
Cored 3697 $\frac{1}{2}$ -3710 $\frac{1}{2}$ Rec. 13'	
All drk grey shale & greyish green shale. Reamed core hole 3697 $\frac{1}{2}$ -3710 $\frac{1}{2}$	
drk grey pyritic shale	3725
drk greyish green shale	3750
lime crystalline grey & brown	3760
Top Lansing lime	3750
lime oolitic grey & brown	3765
lime	3811 Total Depth.