

24-25-14W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm Kipp "B" No. 1

SEC. 24 T. 25 R. 14W
NWc, NW
330' S & 330' E of NW Cor.

Total Depth. 3992 P.B. 3976
Comm. 6-11-46 Comp. 6-22-46
Shot or Treated. Acidized 2000 gal. 7-1-46
Contractor.
Issued. 8-24-46

County. Stafford
KANSAS



Elevation. 1970 ft

Production. B.H.P. Gauge Pot. 3000
Bbls oil, no wtr, 24 hrs.

Figures Indicate Bottom of Formations.

sand	75
sand	230
red bed & shale	660
red bed	835
anhydrite	845
shale	1400
salt & shale	1520
shale & lime shells	1840
shale & shells	1995
lime & shale	3674
lime	3996
3996 Rot. $\gamma\gamma$ = 3992 SIM	
Total Depth	P.B. 3976

Tops:

Lansing	3670
Penetration	322
Perf. Pen. Lansing	203

Drilled float; no com.
below float. Set retainer at
3980 & squeezed with 70 sacks
com. 25 sacks behind casing at
2000 #.
Drilled cement to 3976 SIM.

600' oil in 1 hr. 10 min.
1480' oil in 2 hrs. 5 min.
1530' oil in 2 1/2 hrs.
2090' oil in 4 hrs. 10 min.
2600' oil in 5 1/2 hr.
2850' oil in 7 1/2 hrs.
3550' oil in 9 1/2 hrs.

B.H.P. gauge Pot: 3000 oil,
no wtr, 24 hrs. Ind. Cap.
3253 Bbls.
Hole full oil and flowed in 11 1/2 hrs.

Perf. 60 shots 3862-73
35 shots 3852-58