

27-25-14W

SKELLY OIL CO.
T. A. Toland No. 1.

SEC. 27 T. 25 R. 14 W
CS $\frac{1}{2}$ NE NW
990' f NL 660' f EL NW $\frac{1}{4}$

Total Depth. 3906'
Comm. 7-1-42 Comp. 8-5-42
Shot or Treated.
Contractor. Bodine Drlg. Co.
Issued. 10-3-42

Rotary O-3858
Cable 3858-3906

County. Stafford



CASING:
8 5/8" 426' Cem.
5 1/2" 3855 $\frac{1}{2}$ ' SLM Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface soil, clay, sand	40	tested 3 hrs, no oil
sand	220	or wtr
red bed	840	lime hd gy, no por.
anhydrite	870	or saturation 3858-3863
red bed	900	lime hd gy, w/50%
shale & shells	1375	shale dk, no por.
salt & shells	1500	or saturation 3868
salt & shale	1550	lime gy w/40% shale
shale & lime	2210	dk 3873
sdv lime	2240	lime gy w/10% shale
lime	2265	dk 3878
shale	2275	lime gy w/30% shale
lime	2330	dk 3891
shale & lime	2400	lime gy w/30% shale
lime	2450	dk, bailed & tested
lime & shale	2550	3 hrs, 25 gallons wtr
shale	2635	w/scum of oil 3895
shale & lime	2805	lime lgt gy oolitic,
shale	2925	slight porosity, no
shale & lime	2960	increase 3900
lime	3080	lime lgt gy w/30% dk
shale	3150	gy sh b, tested 1 hr,
lime	3210	1 $\frac{1}{2}$ BW w/scum of oil 3906
lime & shale	3230	Total Depth.
lime	3325	
cherty lime	3370	
lime	3600	
shale	3630	8-10-42 5000 Gals. Acid
shale dk gy	3712	3855 $\frac{1}{2}$ -89
lime med hd gy cryst,		8-17-42 Perf. 5 $\frac{1}{2}$ " csg by
slight porosity	3721	Lane-Wells w/35 holes
lime hd gy	3737	from 3757-64. After
lime med sft gy		perforating, showed
oolitic	3749	a little wtr & no oil,
lime med hd gy cryst,		then perforated from
no porosity	3759	3737 to 3749 w/60 holes
lime med sft gy		no show of oil & no
oolitic	3764	increase in wtr
lime hd gy cryst	3790	8-18-42 1000 Gals. Acid
lime sft gy oolitic,		3737-49 & 3757-64
porous	3798	8-24-42 1000 Gals. Acid
lime hd gy cryst		3737-49
cherty	3807	8-30-42 perf. 5 $\frac{1}{2}$ " csg w/
lime sft gy oolitic,		45 holes by Lane-Wells
porous & stained	3820	3712-21, no shows of
lime hd gy cherty,		oil or wtr
no porosity	3825	8-30-42 1000 Gals. Acid
lime gy oolitic &		3712-21
cherty, slight poro-		All perforations cemented
sity & stained	3830	off
lime hd gy cherty	3840	
shale dk gy	3857	3737-49 porous & stained
lime med sft oolitic	3859	3759-64 porous & stained
lime hd gy cherty,		3857-59 porous & stained
no porosity	3860	3888-91 rainbow sh oil
Correction: 3860 SLM ro-		
tary table equals 3858		Tops: Lansing lime 3712
SLM derrick floor		Lansing pay 3855 SLM