

27-25-14W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- SKELLY OIL CO.
Farm. A.L.Wiles

No. 2

SEC. 27 T. 25 R. 14W
NW NE SW
330' FNL 990' FEL SW 1/4

Total Depth. 3915' PB 3881'

Comm. 1-26-60

Comp.


2-8-60

County Stafford
KANSAS

Shot or Treated.

Contractor. Chas. Hulme Drlg.

Issued. 6-11-60



Elevation. 1981' DF

CASING:
8 5/8" 821' w/450 sx cem.
5 1/4" 3915' w/150 sx cem.

Production. 47 BOPD

Figures indicate Bottom of Formations.

surface soil, sand	35
sand, gravel	215
red beds	495
red bed, shells	761
red bed	820
anhydrite	821
anhydrite, shale	1120
shale	1410
shale, shells	1720
shale, lime	2168
lime	2595
lime, shale	3145
lime	3210
lime, shale	3358
lime	3392
lime, shale	3435
lime	3518
lime, shale	3757
lime	3844
lime, slighty cherty,	
tr. of free oil	3851
lime	3857
lime, shale	3925
Correction to Welex TD	3915
Total Depth	3915
PB	3881

Producing Formation:
Lansing Lime 3847-3854'

Ran Welex Survey.

TOPS:

Heebner shale	3526
Brown lime	3678
Lansing lime	3706

DST #1 - 3841-3857'

PERF: #1 3847-3854'

TREATMENT: #1 - (Acid) - 3847-3854'

" #2 - ? - 3847-3854'