

KANSAS DRILLERS LOG


API No. 15 — 185 — 20861
County Number

S. 28 T. 25S R. 14W E W

Loc. NE SW NW

County Stafford

640 Acres
N



Locate well correctly

Elev.: Gr. 1997

DF 2000 KB 2002

Operator
Alpine Drilling & D.J. Wilson

Address
800 Bitting Bldg. Wichita, Ks. 67202

Well No. #B-1 Lease Name Waters

Footage Location
990 feet from (N) ~~XX~~ line 990 feet from (W) line

Principal Contractor Husky Drilling Co., Inc. Geologist Jon Williams & Jeff Burk

Spud Date October 17, 1978 Total Depth 4299 P.B.T.D.

Date Completed October 25, 1978 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	28#	293	common	300	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

Operator Alpine Drilling & D. J. Wilson

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Dry Hole

Well No. 1

Lease Name Waters "B"

S 28 T 25 S R 14 W E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
---------------------------------------	-----	--------	------	-------

LOG TOPS

Topeka	3170	-1168
Heebner	3594	-1592
Toronto	3612	-1610
Douglas	3633	-1631
Brown Lime	3741	-1739
Lansing	3766	-1764
B/Kansas City	4040	-2038
Miss	4180	-2178
Kinderhook Shale	4219	-2217
Viola	4269	-2267
LTD	4299	-2297

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Jon T. Williams, Jr. Signature

President

Title

October 25, 1978

Date



28-25-14W

800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

October 26, 1978

WELL LOG-----Waters-B #1

Located: NE SW NW of Sec. 28-25S-14W
Stafford County, Kansas.

OWNER: Alpine Drilling & Dwight J. Wilson
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: October 17, 1978
COMPLETED: October 25, 1978

Rotary Total Depth: 4297'

LOG

CASING RECORD:

0 - 913 Sand & shale
913 - 930 Anhydrite
930 - 1890 Shale & Shells
1890 - 3926 Shale & Lime
3926 - 3960 Lime
3960 - 4019 Lime & Shale
4019 - 4126 Lime
4126 - 4297 Lime & Shale

Ran 7 jts. 8-5/8", 28#, 8V, Rge 3
used csg., tallied 285.97', set
@ 293' KB w/300 sx common, 2% gel,
3% cc, circulated - plug down @
10:30 p.m. 10-17-78 by Allied.

Plugged 10-25-78