

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


30-25-14W

SEC. 30 T. 25 R. 14W
C NE SW

Company- GLICKMAN OIL COMPANY
Farm- Childs No. 1

Total Depth. 4545'
Comm. 10-31-62 Comp. 11-14-62
Shot or Treated.
Contractor.
Issued. 4-27-63

County Stafford
KANSAS



Elevation. 2005 KB

Production. 2,655,000 CFG

CASING:

8 5/8" 292' cem w/250 sx.
5 1/2" 4540' cem w/125 sx.

Figures Indicate Bottom of Formations.

sand	230
shale & red bed	290
red bed	946
shale w/shells	1410
shale & shells	1780
shale & lime	1990
lime & shale	2115
shale & lime	2410
lime & shale	2825
shale & lime	3005
lime & shale	3811
lime	3840
lime & shale	2865
lime	3970
lime cherty	4005
lime	4174
lime & shale	4221
chert	4240
shale & chert	4265
shale	4316
Viola	4466
Simpson	4518
Arbuckle	4545
Total Depth	

TOPS: LOG

Anhydrite	956
Ft. Riley	2222
Howard	3132
Topeka	3196
Heebner	3623
Toronto	3642
Douglas	3662
Brown Lime	3774
Lansing	3800
Base Kansas City	4078
Mississippi	4221
Kinderhook	4241
Viola	4306
Simpson	4463
Arbuckle	4518