

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


33 25-14W

Company- DUNNE-GARDNER DRILLING CO.
 Farm- Southards No. 1

SEC. 33 T. 25 R. 14W
 NW NW SW

Total Depth. 4493'
 Comm. 4-29-63 Comp. 5-13-63
 Shot or Treated.
 Contractor. Dunne-Gardner Drilling Co., Inc.
 Issued. 4-11-64

County Stafford
 KANSAS



Elevation. 2000' KB

Production. 3100 MCFG

CASING:

8 5/8" 599' cem w/500 sx.
 4 1/2" 4041' cem w/600 gal. Latex

Figures Indicate Bottom of Formations.

sand	200
shale blue & sand	305
redbed	599
shale blue & redbed	927
Anhydrite	940
redbed & some lime	1015
redbed, shale & shells	1750
lime & shale	3040
shale-lime strks.	3140
lime & shale	3694
shale & sand	3785
li e	3867
lime, shale & chert	3924
lime	4215
chert	4225
lime & chert	4256
shale	4300
chert & lime	4312
shale & chert	4321
chert & lime	4370
shale & some chert	4402
sand	4410
shale & lime	4467
lime & chert	4493 RTD
Total Depth	

TOPS: LOG

Heebner	3603
Toronto	3621
Douglas	3640
Brown Lime	3761
Lansing	3790
Base Kansas City	4062
Mississippi	4194
Kinderhook	4233
Viola	4269
Simpson	4377
Arbuckle	4444