


Company. AYLWARD DRILLING CO. ET AL
Farm. Knudsen No. 1

6-25-15W
SEC. 6 T. 25 R. 15W
NE NE SW

Total Depth. 4581'
Comm. 8-12-59 Comp. 8-26-59
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 10-24-59

County Stafford
KANSAS



CASING:
8 5/8" 230' cem w/200 sx.

Elevation. 2055' KB

Production. Dry

Figures indicate Bottom of Formations.

sand & clay	50
sand	210
blue shale	300
red bed w/gyp	480
sand	540
red bed	990
Anhydrite	1015
red bed, shale & shells	1250
shale & shells	1730
salt & shale	1795
shale w/lime streaks	2025
lime	2480
lime & shale	2670
shale & lime	3130
lime & shale	3610
lime	3640
sandy lime	3695
shale & lime	3796
lime & shale	3833
lime	3921
lime (chalky)	3990
lime	4132
lime w/shale	4201
lime & shale	4273
chert, lime & shale	4321
lime	4346
lime & shale	4380
lime	4433
lime & shale	4581
Total Depth	

TOPS:
Heebner 3648
Toronto 3668
Douglas 3687
Brown Lime 3790
Lansing 3799
Base Kansas City 4126
Conglomerate 4192
Kinderhook 4226
Viola 4288
Simpson 4464
Arbuckle 4541

DST 4191-4220', op 1 hr., gas to surf.
in 40 mins., too weak to meas. rec. 45'
GCM, IBHP 1525#, FBHP 1030#, FP 170#-170#.