

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


11-25-15W

CITIES SERVICE OIL CO.  
Damerell No. 1.

SEC. 11 T. 25 R. 15 W  
CNE SW  
660'S 660'W Center

Total Depth. 4085' PB 3907'  
Comm. 1-22-43 Comp. 2-25-43  
Shot or Treated, 3-2-43 4000 Acid  
Contractor. Corbett-Barbour Drlg. Co.  
Issued. 6-5-43

County. Stafford



CASING:

10<sup>3</sup>/<sub>4</sub>" 205' Cem.  
7" 3951' Cem.  
(Pld 2279' 11" of 7" csg)

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	0-155	Plugged back to 3977 w/rock
shale & shells	205	& 6 sx cement
shale	215	Acidized 4000 Gals. 3951-77
iron	240	Pmpd 100% wtr
sd shale	450	Plugged back w/crushed rock
red bed	960	3977-3958 & cem. w/4 sx
anhydrite	980	3958-3932
shale & shells	1640	
shale & lime	1825	3-11-43 Perf. 24 shots 3919-
lime brkn	2000	23 <sup>1</sup> / <sub>2</sub> ; 100' fluid 5 min.,
lime	2165	2750' fluid in 50 min.,
lime & shale	2265	total fillup 3100' fluid
lime brkn	2385	(600' oil & 2500' wtr)
lime	2420	
lime brkn	2505	3-13-43 pmpd 16 B. fluid
lime	2615	(5% oil) per hr
shale & shells	2630	3-14-43 pmpd 16 B. fluid
lime & shale	2670	(tr. oil) per hr
lime	2700	
shale	2765	Cemented back 3932-3907
shale & shells	2778	w/5 sx
lime w/strks shale	2840	Set Lane-Wells plug at 3875
lime brkn & shale	2915	
lime brkn	2980	3-20-43 Perf. 16 shots
lime & shale	3040	3850-53; 950' fluid in 12
lime	3210	min., good sh gas; 1800'
shale & lime	3255	wtr, 1 hr. Set Lane-Wells
lime brkn	3275	plug at 3818
shale & lime	3350	
lime	3403	3-22-43 Perf. 11 shots
brkn lime & shale	3460	3797-3806, no fluid;
lime	3485	12 shots 3806-10 <sup>1</sup> / <sub>2</sub> , no
lime brkn	3585	fluid; 11 shots 3810 <sup>1</sup> / <sub>2</sub> -15,
lime	3660	100' wtr w/slight sh oil
shale & lime	3700	in 20 min; 2000' wtr & sh
shale	3775	oil in 18 hrs
lime	3806	
3806=3799 SIM		
lime	3905	
lime cored(rec. 4')	3913	
lime	3940	

3940 Rot. TD=3956 SIM	
lime	3990
lime & shale	4008
lime	4040
shale dk	4046
lime brkn	4070
shale	4085
Total Depth.	

Corr. Top Lansing 3783  
Base Kansas City 4070