


Company- TOMLINSON-KATHOL, INC.
 Farm- Grunder No. 2

SEC. 11 T. 25 R. 15W
 NW NE NE

11-25-15W

Total Depth. 4434'
 Comm. 9-29-59 Comp. 10-18-59
 Shot or Treated.
 Contractor.
 Issued. 1-9-60

County Stafford
 KANSAS



CASING:

8 5/8" 281' cem w/230 sx.
 5 1/2" 4431'

Elevation. 2018' RB

Production. 594 BOPD

Figures indicate Bottom of Formations.

sand	159
clay & shale	241
shale	281
WOC	281-312
red bed	935
shale	963
Anhydrite	1000
shale	1820
lime	1844
lime streak & shale	2018
shale	2157
lime	2180
sand	2205
lime	2260
shale & lime	2450
shale & lime	2565
shale	2714
shale & lime	2880
shale	3285
shale & lime	3457
lime	3623
lime & shale	3728
lime	4107
lime & shale	4164
shale	4179
Mississippian	4220
shale	4269
chert	4344
shale & lime	4373
sand	4414
sand & shale	4420
shale	4434 RTD
Total Depth	

TOPS:

Topeka	3399
Heebner	3600
Toronto	3618
Brown Lime	3746
Lansing	3767
Base Kansas City	4027
Mississippi	4179
Base Mississippi Lime	4222
Viola	4269
Simpson	4365
Arbuckle	4429