


Company- STRATA DRILG. & JOHN P. JENNINGS
Farm- Childs No. 1

SEC. 17 T. 25 R. 15W
C NE NE

17-25-15W

County Stafford
KANSAS

Total Depth. 4580'
Comm. 5-2-59 Comp. 5-16-59
Shot or Treated.
Contractor. Strata Drilg.
Issued. 10-3-59



Elevation. 2043' RB

Production. 4,800,000 CFG

CASING:

3 5/8" 320' cem w/225 sx.
5 1/2" 4290' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay & sand	160
shale	300
shale & shells	321
red bed & shale	840
red bed & shells	990
Anhydrite	1006
shale & shells	1640
shale	1897
shale & lime	3349
chalky lime & shale	3467
lime & shale	3568
lime	3606
lime & shale	3875
lime	4257
lime & chert	4270
lime	4368
chert & lime	4415
lime	4480
lime & shale	4520
lime	4580
Total Depth	

TOPS:	
Heebner	3649
Brown Lime	3800
Lansing	3811
Conglomerate	4198
Mississippi	4229
Viola	4375
Simpson	4475
Arbuckle	4556

DST #1 4200-4215', op 30 min., weak blow
15 mins., rec. 10' mud. IFP 0#, FFP 0#,
BHP 0#/20 min.

DST #2 4242-4270', op 1 hr., good blow
thruout test, gas to surf. in 50 mins.
Rec. 15' mud. IFP 0#, FFP 0#, BHP 1160#/20 mins.

DST #3 4276-4310', op 15 mins., weak blow
4 mins., rec. 110' mud. IFP 0#, FFP 0#,
BHP 0#,

DST #4 4225-4240', op 1 hr., gas to surf.
in 2 mins. Stabilized at 1, 710,000 CFG.
Rec. 30' gas cut mud. IFP 440#, FFP 440#,
BHP 1240#/30 mins.