

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


18-25-15W

Company- CHARLES HULME DRILLING CONTRACTOR  
Farm- Piland No. 1

SEC. 18 T. 25 R. 15W  
SE SE SE

Total Depth. 4651'  
Comm. 2-2-55. Comp. 2-17-55  
Shot or Treated.  
Contractor. Garvey Drlg. Co.  
Issued. 4-2-55

County Stafford  
KANSAS



Elevation. 2053' RB

CASING:

8 5/8" 375' cem w/275 sx

Production. Dry

Figures indicate Bottom of Formations.

sand & gravel	200
sand, shale & red bed	375
shale & red bed	730
red bed	1020
anhydrite	1039
shale & shells	1760
lime & shale	2080
lime	2185
lime & shale	2425
lime	2515
shale & shells	2690
lime & shale	2845
shale & shells	3110
lime & shale	3275
shale	3400
lime & shale	3645
lime	4110
lime, shale & shells	4170
lime	4275
lime & sand	4293
lime, sand & chert	4330
lime & chert	4348
lime & shale	4368
lime, shale & chert	4478
chert	4597
shale	4622
lime	4651
Total Depth	

#1 packer set at 4269', Total Depth 4293',  
tool open 30 mins., weak blow for 3 mins.  
Rec 20' of mud. no show of oil. BHP 0 in  
15 mins.

Note: All tops corrected to electric log  
measurements.

Tops;	
Anhydrite	1020
Heebner	3701
Brown Lime	3845
Lansing	3858
Base Kansas City	4134
Mississippi	4314
Kinderhook Shale	4346
Viola	4403
Simpson Shale	4540
Simpson Sand	4566
Arbuckle	4622

Drill Stem Test: