


KANSAS DRILLERS LOG *State Geological Survey*
WICHITA, BRANCH
 API No. 15 — County Number 2000

S. 28 T. 25 R. 15 W

Loc. C NE NE

County Stafford

640 Acres
N



Locate well correctly

Elev.: Gr. 2021'

DF KB

Operator
Alpine Drilling Co., Inc.

Address
800 Biting Building Wichita, Kansas 67202

Well No. #1 Lease Name Payton

Footage Location
660 feet from (N) (X) line **660** feet from (E) 000 line

Principal Contractor H-30, Inc. Geologist Jon T. Williams, Jr.

Spud Date September 5, 1975 Total Depth 4570 P.B.T.D.

Date Completed November 14, 1975 Oil Purchaser Koch Oil Gas Purchaser Edwards Co. Gas Co.

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	already set						
Production		4-1/2"	9.5#	4,568'		225	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DP charge	4249' - 4254'
			2	DP charge	4219' - 4229'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracked with 2,000 gal. pad; 5,000 gal. @ 1# of 20-40 sand; 2,000 gal. @ 1# of 10-20 sand, drop 15 7/8" RCN balls	4219' - 4299' & 4249' - 4254'
Acidized w/500 gal. 15% MCA acid	4249' - 4254'
Acidized w/750 gal. 15% MCA acid	4219' - 4229'

INITIAL PRODUCTION

Date of first production November 14, 1975 Producing method (flowing, pumping, gas lift, etc.) Flowed

RATE OF PRODUCTION PER 24 HOURS
 Oil 26 bbls. Gas 120,000 MCF Water 0 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Sold Producing interval (s) 4214' - 4229' & 4249' - 4254'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

