

30- 25-15W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- CHIEF DRILLING CO., INC.
 Farm- Lamb No. 1

SEC. 30 T. 25 R. 15W
 C SW SE

Total Depth. 4395'
 Comm. 6-23-60 Comp. 7-4-60
 Shot or Treated.
 Contractor. Chief Drlg. Co.
 Issued. 10-15-60

County Stafford
 KANSAS



CASING:
 8 5/8" 402' cem w/140 sx.
 4 1/2" 4394' cem w/100 sx.

Elevation. 2035' DF

Production. 75 BOPD

Figures Indicate Bottom of Formations.

sand & shale	200
sand & clay	402
redbed with sand strks	660
sand	715
redbed	990
Anhydrite	1015
shale & shells	1975
lime & shale	2125
lime	2225
lime & shale	2375
lime	2465
lime & shale	3325
shale with lime	3500
lime	3690
shale & lime	3727
shale	3835
lime	4150
shale & lime	4272
shale	4279
shale with sand strks	4298
sand	4329
chert & shale	4347
shale	4375
chert	4395 RTD
Total Depth	

TOPS:

Anhydrite	990
Heebner	3690
Toronto	3707
Douglas	3727
Brown Lime	3835
Lansing-Kansas City	3843
Cherokee Shale	4272
Cherokee Sand	4279
Conglomerate Sand	4298
Kinderhook Shale	4347
Viola	4375