

30. 25-15W

Company. COLORADO OIL & GAS CORP.
 Farm- Lamb No. 1

SEC. 30 T. 25 R. 15W
 SE NW NE

Total Depth. 4400'

Comm. 9-9-58


Comp. 9-23-58

Shot or Treated.

Contractor. Glenn W. Peel Drilg. Co.

Issued. 5-16-59

County Stafford
 KANSAS



Elevation. 2044' KB

Production. 1,700,000 CFG

CASING:

8 5/8" 328' cem w/275 sx.
 5 1/2" 4398' cem w/125 sx.

Figures indicate Bottom of Formations.

surface clay & sand	30
sand	200
shale & shells	328
shale	425
red bed	990
Anhydrite	1025
shale & shells	1490
salt	1680
shale	1890
lime	2385
lime & shale	2585
shale & lime	3170
shale	3310
lime	4320
lime & shale	4360
chert & shale	4400
Total Depth	

TOPS: ELECTRIC

Anhydrite (scout)	970
Heebner	3682
Lansing	3844
Conglomerate Shale	4262
Kinderhook Shale (Basal Penn)	4325
Viola	4354

Run Gamma Ray Neutron, Laterolog.

Perf. 32/4276-4284'.

Trtd w/500 gal mud acid. Fraced w/10,000
 lease crude & 8500# sd.

DST 3863-3880', op 120 mins., good blow
 2 hrs. rec 35' OCMW & 60' MW & 120' W w/
 scum of oil. IFP 60#, FFP 90#, SIBHP
 1440#, FBHP 1020#.

DST 4259-4273', op 60 mins, no blow,
 rec. 5' mud, IFP 42#, FFP 42#, IBHP 42#,
 FBHP 42#.

DST 4276-4290', op 75 mins, gas in 3",
 734 MCF in 5", incd to 900 MCF @ end of
 20", remained steady. Rec. 70' GCM, no
 oil. IFP 139#?, IFP 111#, IBHP 1456#,
 FBHP 1423#.