

Company- D. R. LAUCK OIL CO.
Farm- Kennedy No. 1


SEC. 34 T. 25 R. 15W
C NE SE

34-25-15W

Total Depth. 4610'
Comm. 7-27-60
Shot or Treated.
Contractor.
Issued. 3-25-61

Comp. 8-9-60

County Stafford
KANSAS



CASING:
8 5/8" 279' cem w/225 sx.

Elevation. 2024' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand	230
shale	300
red bed	480
sand & red bed	600
red bed	975
Anhydrite	995
shale & shells	1690
Anhydrite & shale	1940
Anhydrite	2050
lime & shale	2395
broken lime	2450
shale & lime	2765
shale & shells	3125
shale & lime	3315
lime & shale	3425
lime	3475
lime & shale	3705
shale-lime streaks	3810
shale	3895
lime	4154
shale & lime	4175
lime & shale	4301
chert	4355
shale & chert	4440
chert, shale & lime	4475
Viola	4535
shale	4581
lime	4610 RTD
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Heebner	3688	3689
Brown Lime	3829	3828
Lansing	3849	3847
Base Kansas City	4146	4148
Mississippian	4302	4302
Kinderhook	4330	4326
Viola	4440	4439
Simpson	4530	4527
Arbuckle	4581	4572

DST #1 4303-4315', op 30 min, weak blow
30 min, rec. 5' mud, IFP 15#, FFP 15#,
BHP 35#/20 min.