

1-25-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. THE GULF OIL COMPANY
Farm- L. Reese No. 2

SEC. 1 T. 25 R. 15W
SW NE NW

Total Depth. 4395'
Comm. 6-25-60 Comp. 7-10-60
Shot or Treated.
Contractor. Sierra Petroleum Co., Inc.
Issued. 9-3-60

County Stafford
KANSAS



CASING:

8 5/8" @ 328' w/120 sks. cem.
5 1/2" @ 4393.05' w/250 sks. cem.

Elevation. 2021' RB

Production. 73 BOPD

Figures Indicate Bottom of Formations.

sand	100
shale	405
red bed	956
Anhydrite	981
shale & shells	1395
salt	1423
shale & shells	1860
lime & shale	3505
lime	3568
lime & shale	3725
lime	4213
Kinderhook	4250
shale & chert	4306
lime	4344
Simpson	4389
Arbuckle	4395
Total Depth	

SCOUT TOPS:

Heebner	3593
Lansing	3754
Base Kansas City	4020
Mississippi	4159
Kinderhook	4206
Viola	4260
Simpson	4360
Arbuckle	4389