



State Geological Survey
WICHITA BRANCH

3-25-15W

800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

September 20, 1978

WELL LOG.....Barstow D#1

Located: C NW NE NW, Section 3-25-15W Stafford,
County, Kansas

OWNER: Barnett Oil Company
ROTARY DRILLING CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: 9-08-78
COMPLETED: 9-16-78

TOTAL DEPTH: 4430'

LOG

0 - 40	Sand & Clay
40 - 340	Stone & Shale
340 - 480	Shale & Shells
480 - 780	Shale w/hard sand streaks
780 - 960	Shale & Sand
960 - 1675	Shale
1675 - 2055	Shale & Shells
2055 - 3290	Shale & Lime
3290 - 3564	Lime & Shale
3564 - 3745	Lime
3745 - 3974	Lime & Shale
3974 - 4102	Lime
4102 - 4370	Lime & Shale
4370 - 4430	Lime

CASING RECORD

Ran 8 jts., 8-5.8", 28#,
Rge 2 & 3, used casing, tallied
331.27', set @ 338'KB w/275
sx 60/40 pozmix w/2% Gel, 3%
cc - circulated - plug down @
7:45 p.m. 9-8-78 by Allied.

Plugged.