

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

3 - 25 - 15W

SINCLAIR PRAIRIE OIL CO.
Cora M. Smith No. 1.

SEC. 3 T. 25 R. 15 W
SW NE NW
990'f N & E Lines NW $\frac{1}{4}$

Total Depth. 4495'
Comm. 8-2-43 Comp. 8-28-43
Shot or Treated.
Contractor. Harbar Drlg.Co.
Issued. 10-2-43

County. Stafford



CASING:
10 $\frac{3}{4}$ " 959' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand	220	Cored 4440-50 rec.9'
shale & shells	950	Simpson green shale 4440-48
anhydrite	980	Cored 4450-60 rec.9 $\frac{1}{2}$ '
shale & shells	1245	top 5' shale
shale & shells	1700	btm 4 $\frac{1}{2}$ ' dolomite
salt	1760	Cored 4460-75 rec.4 $\frac{1}{2}$ ' no sh
shale & shells	1820	of oil, spotted porosity
lime	2435	Drilled to 4495, T.D.
shale	2485	Ran Schlumberger, no oil
lime	2915	shows, sh wtr in Lan-K.C.
shale & lime	3150	& Arbuckle
lime	3170	
lime & shale	3255	
lime	3290	
lime & shale	3335	
lime	3435	
lime brkn	3460	
lime	3640	
shale	3780	
lime	3941	
lime sft	3958	
lime	4160	
shale	4209	
chert	4215	
shale	4223	
conglomerate	4290	
lime cherty	4318	
chert	4335	
lime	4440	
shale	4448	
sand	4450	
shale	4455	
dolomite-shale	4460	
lime	4495	

Total Depth.

Tops:	Rig Fl.	Sur.Lev.
Kansas City	3780	3777
Conglomerate	4170	4167
Viola	4270	4267
Arbuckle	4455	4452
T.D.	4495	4492