

5-25-15W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- **ANSCHUTZ DRILLING COMPANY, INC.**
 Farm- Barstow No. 1

SEC. 5 T. 25 R. 15W
 SW SW NE

Total Depth. 4592

Comm. 10-8-52


Shot or Treated.

Contractor.

Issued. 12-6-52

Comp. 10-28-52

County Stafford
 KANSAS



CASING:

8 5/8" 327' cem. w/256 sx
 5 1/2" 3908' cem. w/100 sx

Elevation. 2075 RB
 2072 (Ind.)
 Production. Dry

Figures Indicate Bottom of Formations.

sand	250
sand & shale	325
shale	370
sand & shale	450
red bed	900
shale & shells	1028
anhydrite	1046
shale & shells	1875
lime & shale	2320
shale	2330
lime & shale	3360
lime	3725
lime & shale	3831
lime	4100
lime & shale	4255
shale, lime & chert	4285
cherty lime	4305
lime & shale	4392
lime	4490
lime & shale	4560
lime	4592
Total Depth	

Tops:

Anhydrite	1000
Heebner	3677
Brown Lime	3820
Lansing	3830
Base-Kansas City	4103
Shaley Conglomerate	4196
Cherty Congl.	4231
Kinderhook (?) Sand	4285
Kinderhook Shale	4298
Viola	4372
Simpson Shale	4498
Arbuckle	4573