

5-25-15W

COMPANY KEWANEE OIL

SEC. 5 T. 25 R. 15W

FARM Barstow

NO. 1

LOC. C NW SW

660'FWL & 1980 FSL SW $\frac{1}{4}$

TOTAL DEPTH 4298'

COUNTY Stafford

COMM. 7-3-66


COMP. 7-15-66

SHOT OR TREATED

CONTRACTOR Gabbert-Jones

ISSUED 1-6-68

KANSAS



CASING

20 10
15 8 5/8" 275.39' cem w/ 225 sx
12 6
13 5

ELEVATION 2047' DF

PRODUCTION Dry/Kind

FIGURES INDICATE BOTTOM OF FORMATIONS

Anhydrite	992	+1053	Tarkio	3036	-991
Hollenburg	2063	-18	Elmont	3087	-1042
Herington	2097	-52	Howard	3173	-1128
Winfield	2158	-113	Topeka	3250	-1205
Towanda	2226	-181	Queen Hill	3553	-1508
Fort Riley	2270	-225	Heebner	3656	-1611
Base Florence	2363	-318	Toronto	3675	-1630
Wreford	2397	-352	Douglas	3692	-1647
Council Grove	2452	-407	Brown Lime	3801	-1756
Cottonwood	2585	-540	Lansing	3811	-1766
Neva	2651	-606	Base Kansas City	4078	-2033
Foraker	2722	-677	Conglomerate Sand	4211	-2166
Waubaussee	2900	-855	Mississippian	4246	-2201
Langdon	2962	-917	Kinderhook Sand	4298	-2253

CASING RECORD

Ran 271.07' of 8-5/8" casing set at 275.39' C.M. Cemented with 225 sacks
50-50 pozmix, 1/4# Flocele per sack and 3% HA-5. Cement Circulated.

FORMATION RECORD

0- 215	Sand
215- 280	Shells and Blue Shale
280- 991	Red Bed
991-1005	Anhydrite
1005-1150	Red Bed and Shale
1150-1820	Shale
1820-1995	Shale and Lime Streaks
1995-2285	Shale and Lime
2285-2445	Shale and Lime Streaks
2445-2925	Shale and Lime
2925-2985	Lime
2985-3460	Lime and Shale
3460-3478	Lime and Chert
3478-3535	Lime and Shale
3535-3654	Lime