

25-25-16W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SOUTHLAND ROYALTY CO.
Farm- Johnson No. 2

SEC. 25 T. 25 R. 16W
C SW SW

Total Depth. 4449'
Comm. 4-30-59 Comp. 5-12-59
Shot or Treated.
Contractor. Lauck Drlg.
Issued. 10-3-59

County Edwards
KANSAS



Elevation. 2052' DF

Production. 212 BOPD

CASING:

8 5/8" 348' cem w/300 sx.
5 1/2" 4445' cem w/145 sx.

Figures indicate Bottom of Formations.

clay & sand	30
sand	200
shale	348
red bed	1025
Anhydrite	1040
red bed & shale	1240
red bed	1475
shale & shells	1980
shale & lime	2145
lime & shale	2675
shale & lime	3505
lime & shale	3530
sandy lime & shale	3585
lime & shale	3775
shale & lime	3910
lime & shale	3975
lime	4180
lime & shale	4240
shale & lime	4329
sand, shale & chert	4370
shale	4374
chert & shale	4445 RTD
chert & shale	4449
Total Depth	

TOPS: SCOUT

Heebner	3722
Brown Lime	3863
Lansing	3882
Cherokee Shale	4320
Cherokee Sand	4333
Mississippi	4356
Kinderhook Shale	4318
Kinderhook Sand	4424
Viola Chert	4430
Viola Lime	4440